

# APP Configuration 1 – Download & Registration



## Step 1:

Search "Hyxipower" in  
APP store  
Google play

Video:

[webfile.hyxipower.com/soft/20231129/HYXiPOWER-APP\\_Installer-registration\\_Ver1.0-20231103.mp4](http://webfile.hyxipower.com/soft/20231129/HYXiPOWER-APP_Installer-registration_Ver1.0-20231103.mp4)

## Step 2 : Register Now - European Server - Register as Organization.

More ▾

**HYXiPOWER**

Email/Phone No.

Password

Forgot Password? **Register Now**

I agree to the [Terms of Use](#) and I have read the [Privacy Policy](#)

**Log In**

**Experience**

**Select Role**

Please select the relevant server for your area

**Select Your Server European Server** >

If Your Role Is An Installer Or A Distributor, Please Register For The Following Role.

**Register as Organization** Installer or Distributor >

Register as Owner

**Register as Owner** Plant Owner >

If You Have Only Installed A Balcony Photovoltaic System, Please Register The Following Roles.

**Registered Balcony System Homeowner** Balcony System Owner >

**Register as Organization**

Note: If your organization or company has registered for an organization account in this system, you do not need to register again. Please contact your administrator to add you to the member list

Organization/Company Name **Please Enter**

Registration Method

**Please Enter** @hotmail.com ▾

**Please Enter** **Send**


Complete Info

Password **Please Enter** ▾

Confirm Password **Please Enter** ▾

**Register**

I agree to the [Terms of Use](#) and I have read the [Privacy Policy](#)



# APP configuration 2 - Near-end Commissioning






Step 1: **Update APP** if there' s a notice.

**More – European Server .**

**More- Near-end Commissioning.**

Download the firmware as a backup.






# APP configuration 2 - Near-end Commissioning



**Step 2 : Scan** DCS QR code ,  
**Join** wireless network **DCS-XXXXXXXXXXXX** .

If the scanned barcode cannot be recognized,  
You can also choose **to connect manually** .



# APP configuration 2 - Near-end Commissioning



**IOS**  
Find the WIFI in settings of phone starting with DCS and connect: DCS-XXXXXXXXXXXX, Password is **hyxi0607** or **12345678**, after connected, **return** to the "Hyxipower" APP and select **Next**.

## APP



## WIFI setting interface

## APP




Keep the APP running in the background and enter the WiFi settings page **manually**.

Enter the WiFi password.



Then return to the APP.



# APP configuration 2 - Near-end Commissioning



## Android system :

Find the WIFI in settings of phone starting with DCS and connect: DCS-XXXXXXXXXXXXX;  
Password is **hyxi0607** or **12345678**, after connected, **return** to the "Hyxipower" APP and select **Next**.


### APP



Keep the APP running in the background and enter the WiFi settings page **manually**.


Enter the WiFi password.

### WIFI setting interface



Then return to the APP.

### APP



# APP Configuration 2 - Near-end Commissioning






**Step 3** : Device login, initial password: **hyxi0607**. (If the password is incorrect, please try **12345678** ) Log in and change the password, then save. (Record the new password. If you forget the password next time, you can **quickly press the DCS RESET button 4 times to restore the factory settings**)

# APP Configuration 2 - Near-end Commissioning



Step 4 : Quick Settings - **Device Management** , confirm **the SN of DCS** and Inverter and **the meter configuration**.

**Default setting of meter :Grid type : Single-phase; Number: 1; Address :1; Mounting Position: Grid-side.**




# APP Configuration 2 - Near-end Commissioning





Step 5 : **Grid connection settings**, select your **time zone**.

If the the system firmware version is not the latest, to ensure normal running, APP will remind you to click OK to upgrade. It will take 10 minutes. This is mandatory and must be done.






- 1.If the firmware version is low, then APP can' t read the grid information. In this case, the inverter uses the EN50549 connection protection by default.
- 2.After the inverter is upgraded, could choose:  
Netherlands: Netherlands;  
Germany: VDE-AR-N-4105;  
Italy: CEI-021



# APP Configuration 2 - Near-end Commissioning

**Step 6 : Export Control** – Suggested settings: **Enable export control ,Feedin to GRID power upper limitation(w): 0 (If there is a need to inject into the grid, set the corresponding power value)**



# APP Configuration 2 - Near-end Commissioning







**Step 7: On-Grid Work Mode-Mode settings-**The minimum SOC of the battery in the work modes.

**Loop settings :** Set specific work days and work modes for specific periods of the day.

**The default mode is 7 days and 24 hours Self Use mode.**


**If there' s PV panel in the system, suggested to keep the default setting.**



# APP Configuration 2 - Near-end Commissioning




If there is no PV panel in the system ,only battery and inverter, we should Set the Back Up(Grid) mode for at least 2 hours per day to ensure the grid will charge the battery 2 hours everyday.



# APP Configuration 2 - Near-end Commissioning






**Step 8: Off-Grid Work Mode :** When there is no grid voltage in the system, set the minimum value of the battery. Suggested to keep the default setting: 10.



# APP Configuration 2 - Near-end Commissioning



Step 9: **Battery Low SOC Dead Protection**: Enable it. System will charge the battery from grid automatically when its SOC reaches 5%; **Battery Type Settings**: Li-ion.



# APP Configuration 2 - Near-end Commissioning



**Step 10** : WiFi solution: Choose your local **server**, fill in the **Wi-Fi name and password**.


b. LAN Cable solution: Confirm the automatic IP acquisition switch is **ON** for

c. 4G SIM card version.

If the configuration is successful, exit the APP; If it fails, check the system and configure it again.

Android users can automatically obtain the corresponding wifi name

IOS users need to manually input the WiFi name




# APP Configuration-Create Plant for Owner





**Step 1:** Disconnect from the WiFi Microinverter wireless network, select a wireless network that can access the internet normally or use mobile data.



**Step 2:** Log in your organization account.  
**Plant-Add Plant.**







**Step 3:** Click the plus sign. Could choose:  
**Scan/Add By Nearby Online Devices**



# APP Configuration-Create Plant for Owner



**Step 4: Binding User.** The system will automatically determine whether the mailbox has been registered on the platform.





# APP Configuration-Create Plant for Owner



Step 5: Basic Info. **Notice: Photovoltaic installed capacity means the capacity of all the PV panels.**


Step 6: Tariff Type-Currency-Revenue-Done.




# APP Configuration-Check the Status then Exit the Site



## Inverter indicators



Keep green keep blue keep off




### 2.7.1 LED indicator status description

No.	Indicator	Status	Description
1	POWER	ON	Inverter Powered ON
		OFF	Inverter Powered OFF
2	GRID	ON	Grid Normal
		Blink 1	Grid Abnormal
		Blink 2	Grid Disconnected
3	COM.	ON	COM. Normal
		Blink 1	Meter COM. Fault
		Blink 2	COM. Fault With BMS
		OFF	Fault Both Meter & BMS
4	ALARM	OFF	Normal
		Blink 1	Inverter Internal Alarm
		Blink 2	Other Alarm

\* 1 time flashing, interval 1.5 seconds; 2 times flashing, interval 0.2 seconds.

## Battery indicators



25% 50% 75% 100%  
Stay green.

Keep off

Working station Indicator, stay green. When leaving the site, confirm again.

System Status	WORK	ALM
	●	●
Shutdown	Off	Off
Idle state	On 0.5s, off 1.5s	Off
Normal operation	On	On 0.5s, off 0.5s
First level alarm	On	On 0.5s, off 1.5s
Second level alarm	Off	Off
Third level alarm	Off	On


# APP Configuration-Check the Status then Exit the Site

## DCS indicators



Indicator	Status	Description
POWER	ON	Power ON
	OFF	Power OFF
NET	Solid Green	Connected to the server
	Flashing	Connecting to the server
	OFF	Disconnected from the server
COM.	Solid Green	Normal communication with inverter
	Flashing	Communicating with the inverter
	OFF	Communication with inverter failed

# Installation Acceptance



**Step 1:** Select **Plant - User's Plant - Device**, and ensure that the online state of device is correct.

**Step 2:** After installation is completed, continuously monitor for more than half an hour, select **Statistics - Energy Analysis**, view the realtime power statistics curve, and ensure that the Plant has started generating electricity normally.

**After confirming that all the above are normal, it indicates that the device installation and configuration is successful!**