

Three-Phase String Inverter Installation Guide S8K/S10K/S12K-T -General

Delivery and Service Center

品质

创新

高效

共赢

CONTENTS


01 Program Overview

02 Installation Preparation

03 Device Installation


04 App Configuration

1.1 Program Overview-Solution Overview



Before installation, conduct a site survey and, referring to the diagram above, plan the equipment installation positions and wiring scheme in advance.

1.2 Program Overview-String Inverter Introduction



NO.	Name	Explanation
1	LED Indicator Panel	Display the current operating status of the inverter
2	Mounting Bracket	Secure the inverter to the top
3	Bottom Bracket	Secure the Inverter at the Bottom
4	Heat Sink	For inverter ventilation and heat dissipation
5	DC Switch	PV panel DC power input switch
6	DC Switch Lock	DC lock hole reserved

NO.	Name	Explanation
7	DC Input Port	DC input port from PV panels to inverter
8	COM Port1	RS485 communication port
9	Meter Port	Communication port between inverter and meter
10	DRM Port	DRM reserved port (Australia only)
11	DCS Port	DCS connection port
12	AC Port	Inverter AC terminal port

1.3 Program Overview-DCS Introduction



RESET button:

1. Press 2 times to restart
2. Press 3 times to enable local configuration (AP mode);
3. Press 4 times to restore factory settings (Within 1 second between pressing)

Indicator	Status	Description
Power	On	Power ON
	OFF	Power OFF
NET.	Solid Green	Connected to server
	Flashing	Connecting to server
	OFF	Disconnected from server
COM.	Solid Green	Normal communication with inverter
	Flashing	Communicating with inverter
	OFF	Communication with inverter failed

1.4 Program Overview-Meter Introduction



The DTSU666 three-phase energy meter

The DTSU666 three-phase energy meter is an advanced device integrating high-precision metering, remote communication, and intelligent management. Equipped with a high-performance metering chip, this meter ensures accurate power measurement and supports real-time energy monitoring, enabling users to track electricity consumption effectively. Additionally, the DTSU666 features an RS485 communication interface and wireless modules, facilitating remote data exchange and centralized monitoring, thereby significantly enhancing operational efficiency.



Current Transformer

The CT (Current Transformer), as a critical component of the DTSU666 energy meter, employs a non-contact measurement method, enhancing safety and reliability. It enables accurate high-current measurement and adapts to varying current and voltage levels, significantly expanding the meter's application scope.

CONTENTS

01 Program Overview

02 Installation Preparation

03 Device Installation

04 App Configuration

2.1 Installation Preparation-Materials and Tools Preparation



Conduct a site survey and make plans in advance before installation







1. Plan the equipment placement in advance: Determine the mounting position for the inverter.
2. Understand the PV connection status on-site: Check whether photovoltaic (PV) panels are present and whether their current and voltage meet the inverter's specifications. If they exceed the specifications, inform the customer in advance to reduce the number of PV panels to avoid equipment damage.
3. Check the location of the inverter and the main circuit breaker where power enters the house.
4. According to the pre-installation assessment of the site environment, measure the required length of each cable and purchase the necessary cables in advance for installation, as shown in the table on the right.

Important! ! The following cable products are not provided and need to be purchased separately.

No.	Name	Description	Specification
1	PV Cable	Cables used from the photovoltaic panels to the inverter should be multi-core photovoltaic cables with a maximum voltage tolerance of 1100V.	conductor cross-sectional area: 4~6mm ² outer diameter of the cable: 5.5~9mm
2	AC output cable	Used for AC-side wiring of the inverter, outdoor copper-core cable / aluminum-core cable	conductor cross-sectional area: 16-35mm ² copper-core cable /35~50mm ² aluminum-core cable outer diameter of the cable: 20-30mm
3	Ground wire	For equipment grounding use	conductor cross-sectional area≥ 6mm ²

2.2 Installation Preparation-Materials and Tools Preparation

Existing equipment list

No.	Name	Figure	Description
1	Three Phase String Inverter		Includes one inverter main unit and related accessories.
2	DCS		After registering the device to the cloud server, it can be centrally managed through the cloud platform.
3	The DTSU666 energy meter		Measurement of circuit voltage, current, power, etc.
4	Current Transformer		To acquire grid-side AC current for precise inverter power output regulation and anti-islanding protection. Note: The directional arrow must be oriented toward the grid during installation.
5	Ethernet Cable		The device includes a 2-meter CAT5e Ethernet cable as standard. Extended cable lengths must be procured separately if required.
6	Wall-mounted Bracket		Wall-mounted inverter support (mounting bracket included in product packaging)

2.3 Installation Preparation–Tool Installation

Installation Tool



Electric Drill



Heat Gun



Hex Key



Wire Stripper



Hydraulic Pliers



Crimping Tool



Screwdriver



Marker Pen



Utility Knife



Multimeter




Tape Measure



Hammer

Protect Tool



Protective Mask



Safety Glasses



Insulated Safety Shoes



Insulating Gloves

CONTENTS

01 Program Overview

02 Installation Preparation

03 Device Installation

04 App Configuration

3.1 Device Installation- Product Unboxing Inspection

Inverter Unboxing Inspection:



- Check whether the device hardware and ports are intact.
- Check whether the device accessories are intact.

No.	Name
1	Inverter
2	Mounting Bracket
3	Signal Connector
4	AC Connector
5	Hexagon Wrench
6	DC Connector
7	Screws




3.2 Device Installation–Environment Requirements

1. Suitable for both indoor and outdoor installation.
2. -30°C to +60°C, 0~100% relative humidity (RH).
3. Select a shaded location to avoid direct sunlight and protect against rain/snow.
4. Ensure proper ventilation for heat dissipation.
5. The mounting structure must support at least 4 times the inverter's weight.
6. Mount vertically or tilted backward $\leq 15^\circ$ to optimize thermal performance.
7. Do NOT install forward-facing, backward-facing, upside-down, horizontally, or sideways.
8. For multi-unit installations, maintain $\geq 300\text{mm}$ clearance between inverters.



3.3 Device Installation-Inverter Installation

The mounting bracket and inverter can be securely installed in the following ways:



Step 1: Place the wall plate horizontally on the wall, recommend to select the hole position shown in the picture and mark the drilling position.

Step 2: Drill a hole at the location shown, the depth of the hole is about 70mm.

Step 3: Place the expansion tube and install the wall plate using the expansion bolt assembly.


Step 4: Secure the mounting plate with M6 screws.

Step 5: Hang the mounting lugs onto the peg plate and tighten them with M6 screws and finally lock them.

3.4 Device Installation-Inverter Installation








When installing multiple inverters, a distance of at least 300mm should be maintained between two inverters.



Note: Before installing the equipment, please ensure that the photovoltaic panels are installed and the cables have been properly laid.

3.5 Device Installation-Inverter grounding installation



Step 1 : Strip off a certain length of insulation

$L = E + (2-3)mm$.


Step 2 : Pass the cable through the hot melt sleeve and insert it into the terminal block.

Step 3 : Use crimping pliers to tightly connect the terminal blocks and cables .

Step 4 : Adjust the hot melt sleeve to cover the end of the terminal block and the power cord, and use a hot air gun to blow the hot melt sleeve to cover the end of the power cord and terminal block.

Step 5 : Use a screwdriver to fix the ground wire to the inverter ground position.

3.6 Device Installation-DC Connection



Step 1: Turn the DC switch to "OFF" manually.

Step 2: Strip off the insulation layer of all DC cables by about 7mm.


Step 3: Use crimping pliers to bundle the cable ends at the wiring terminals.

Step 4: Pass the cable through the cable gland, insert the insulating sleeve and fasten it. Use a force of 2.5~3N·m to tighten the gland and insulating sleeve.

Step 5: Use a multimeter to check and confirm that the polarity of the photovoltaic string connecting cable is correct.

Step 6: Connect the PV connectors to the corresponding terminals until a click is heard and seal the vacant DC terminals with MC4 waterproof plugs.

3.7 Device Installation-AC Connection



Step 1: Connect the AC output power cable to the AC connector. Stripping requirements.

Step 2: Unscrew the bottom waterproof fixing bolt of the AC connector.


Step 3: Thread the cables through the AC terminal blocks one after the other.

Step 4: Insert the AC terminal blocks into the AC connector and tighten the bottom waterproof fixing bolts.

Step 5: Plug the AC terminal blocks into the AC output port of the inverter.

Step 6: Use a screwdriver to remove the AC connector.

3.8 Device Installation- Meter Connection



Step 1: Place black seal ring on the green Locker.

Step 2: Put red seal ring into the bottle of body inside.

Step 3: Wire stripping.


Step 4: Pass all parts through the wire in the following order.

Step 5: Crimp the 2pin copper core on the green locker and tighten it.


Step 6: Screw all parts together and connect the water-proof 2pin connector to inverter meter port

Caution:

Only the meter models specified by HYXiPower shall be used.



3.9 Device Installation- Meter Connection




U : Line Wire R
V : Line Wire S
W: Line Wire T
N : Neutral Wire

**Wiring Diagram
(Top Side of
Electricity Meter)**

Wiring Diagram (Top Side of Electricity Meter):

- Connect the three-phase live wires and neutral wire between the grid and the inverter as shown in the diagram. The phase sequence of the upper terminals L1, L2, L3 must correspond one-to-one with the lower CT terminals IA (13,14), IB (16,17), IC (19,21). Ensure all CT arrows point toward the grid side.











**Wiring Diagram
(Bottom Side of
Electricity Meter)**

Wiring Diagram (Bottom Side of Electricity Meter):

- For the current transformer (CT) communication wires connected to the three-phase live lines: **the white wire corresponds to I*, and the blue wire corresponds to I.**
- The inverter communicates with the meter via **PIN 2 (A) and PIN 4 (B)** of the COM port.

3.10 Device Installation-DCS Installation



1、DCS Installation (4G Version)

Step 1: Remove the protective cover of DCS and insert the SIM card;

Step 2: Install the waterproof cover of DCS;

Step 3: Remove the waterproof cover at the communication interface of the inverter;

Step 4: Insert DCS into the corresponding communication terminal at the bottom of the inverter and tighten it to ensure it is secure.

2、DCS Installation (WLAN module)

Step 1: Replace the bottom plug of DCS with the WLAN plug.

Step 2: Insert the network cable connector into the network junction.

Step 3: Remove the waterproof cover at the communication interface of the inverter.

Step 4: Insert DCS into the corresponding communication terminal at the bottom of the inverter and tighten it to ensure it is secure.

3.11 Device Installation-Inverter Startup




Figure1

Step 1: Open the circuit breaker on the AC side.

Step 2: Open the circuit breaker on the photovoltaic side.

Step 3: Turn on the DC switch on the inverter.

Step 4: Confirm the indicator light status of the inverter. The indicator light status in Figure 2 is normal.




Figure2

No.	Indicator	Status	Description
1	POWER	ON	Inverter Powered ON
		OFF	Inverter Powered OFF
2	GRID	ON	Grid Normal
		Blink 1	Grid Abnormal
		Blink 2	Grid Disconnected
3	COM.	ON	COM. Normal
		Blink 1	Meter COM. Fault
		Blink 2	COM. Fault With BMS
		OFF	Fault Both Meter&BMS
4	ALARM	OFF	Normal
		Blink 1	Inverter Internal Alarm
		Blink 2	Other Alarms

CONTENTS

01 Program Overview

02 Installation Preparation

03 Device Installation

04 App Configuration

4.1 APP Configuration-Registration




- 1、 Download HYXipowerAPP
- 2、 Register the account of the person in charge of the organization



Register the DCS communication stick to the cloud server through local debugging.

All Hyxipower equipment is managed using the cloud platform. After the equipment is registered to the cloud server, it can be managed uniformly through the cloud platform.



Create a power station for users

You can manage the equipment through the power station and check the equipment status, system power generation and usage, etc.

4.1 APP Configuration-Registration



The entire process requires 2 email accounts: Organization and Owner.

Step 1: Download the APP and **register**

Method 1

Search "Hyxipower" in the Application Store

- APP store (IOS)
- Google play

Method 2

Scan the QR code download the APP



Step 2 : According to the country or region, select **server**, select **organization** , fill in the relevant information and **register**.



4.2 APP Configuration-Near-end Commissioning



Registration

1. Download HYXipower APP .

2. Register the account of the person in charge of the organization.



Near-end
Commissioning

Register the DCS communication stick to the cloud server through local debugging.
All Hyxipower equipment is managed using the cloud platform. After the equipment is registered to the cloud server, it can be managed uniformly through the cloud platform.



Create a Plant

Create a power station for users



You can manage the equipment through the Plant and check the equipment status, system power generation and usage, etc.

4.2 APP Configuration-Near-end Commissioning



Step1: Click **Device Installation** in **Service** interface.

Then scan the QR code of the Data Communication Stick. If failed ,click the Manually Connect.



4.2 APP Configuration-Near-end Commissioning




Step2: Device login, initial password:
hyxi0607. Log in and change the
password, then save it.

If you forgot the password, quickly press
the RESET button on the DCS **4** times to
restore factory settings

< Authentication

Current Device SN 60701233800024

Installer ▼

Password 

[Forgot Password](#)

Log In



4.2 APP Configuration-Near-end Commissioning



Step3: Quick Settings

① **Device Management**: The DCS automatically reads the inverter's **SN and model number**.


Meter settings: 1. Grid type—**Three-phase**; 2. Configure meter—default address 1, install on **grid side**.





4.2 APP Configuration-Near-end Commissioning



Step4: ② **On-grid Settings:** Select the corresponding country's grid-code, then click Next.



Step 5: ③ **Device Settings** - Set feed-in power limit (enable and set to 0 to stop feeding grid).




4.2 APP Configuration-Near-end Commissioning

Step6: ④ **Communication Settings:** Wi-Fi Mode: Enter **Wi-Fi name and password**.

Wired Mode: Ensure automatic IP acquisition is enabled.

4G Mode: The APN, username and password will be recognized automatically, and proceed to next step after setup.



- Completion sign: Green checkmarks show between Device - Router - Cloud platform
DCS shows three steady LED lights

4.3 APP Configuration-Create a Plant



Registration

1. Download HYXipower APP .
2. Register the account of the person in charge of the organization.



Near-end
Commissioning

Register the DCS communication stick to the cloud server through local debugging.

All Hyxipower equipment is managed using the cloud platform. After the equipment is registered to the cloud server, it can be managed uniformly through the cloud platform.




Create a Plant

Create a power station for users


You can manage the equipment through the Plant and check the equipment status, system power generation and usage, etc.

4.3 APP Configuration-Create a Plant


Step 1: Disconnect the phone from the DCS' s WiFi. Make sure your phone has Internet access



Step 2: Log in to the organization account, click "Add Plant"




Step 3: Scan the QR code of the DCS or add it through Recently Debugged Device



4.3 APP Configuration-Create a Plant




Step 4: Add owner - manually add or scan the owner's QR code to bind. Manually add - enter the email address or mobile phone number of the Plant owner. If the owner is not registered, click to help him register and bind. The system will generate a random password and send a text message or email to the registered account



4.3 APP Configuration-Create a Plant

Step 5: Fill in basic information including Plant name, Plant type(**Household Use**), Region, Time Zone, and More information including Photovoltaic Installed Capacity, etc.



The image displays three sequential screenshots of the HYXiPOWER app's 'Add Plant' configuration process.

Screenshot 1: Add Plant - Basic Info

- Progress bar: 1. Add Device (checked), 2. Bind User (checked), 3. Basic Info (active), 4. Price Config.
- *Plant Name: [Input field]
- *Plant Type: Household Use >
- Region: 中国, 浙江省, 杭州市, 滨江区
- Detailed Address: 浙江省杭州市滨江区长河街道滨兴路1399号-大华股份(总部)
- *Time Zone: (UTC+08:00) Beijing, Chongqing, Hong Kong S.A.R., Urumqi >
- Photovoltaic Installed Capacity: Please Enter kWp
- Buttons: Previous, Next


Screenshot 2: Plant Type

- Header: Plant Type
- Text: Please select the correct plant type.
- Options:
 - ☒ **Household Use**
Residential projects dominated by small-to-medium power microinverters, hybrid inverters, and string inverters.
 - ☐ **Industry and Commerce**
Commercial and industrial projects dominated by high-power string inverters.
 - ☐ **Energy Storage**
Projects dominated by commercial & industrial ESS.

Screenshot 3: Add Plant - Price Config

- Progress bar: 1. Add Device (checked), 2. Bind User (checked), 3. Basic Info (checked), 4. Price Config (active).
- Note: Changes to electricity price types, currency units, prices, etc., will take effect immediately. However, the revenue calculation rules for the corresponding plants will take effect the next day. Unable to proceed with revenue estimation without configuring the electricity price.
- Electricity Price Type: Fixed Electricity Price >
- Currency: CNY >
- Revenue Per kWh: Please Enter
- Buttons: Previous, Finish

4.3 APP Configuration-Create a Plant



Step1: Select the **plant**, enter the **user's plant interface**, go to the device interface, and ensure the devices are online and functioning normally.

Step2: After installation, continuously monitor for at least 30 minutes. Select **Statistics**, go to the Energy consumption analysis interface, check the real-time power generation curve to confirm the plant has started normal electricity production.

After all the above checks are confirmed normal, it indicates successful installation and commissioning of the equipment!

THANKS

Delivery and Service Center

品质

创新

高效

共赢